


1 Lighting Plan
Scale: 3/16"=1'-0"

NOTE:
IN THE TOP OF THE CLOCK TOWER
THERE ARE 4 FLUORESCENT UNIT TO
BE CONVERTED TO LED



2 Clock Tower 4 th Floor
Scale: 3/8"=1'-0"

General Notes

1. CONVERT ALL EXISTING FLORESCENT FIXTURES TO LED
2. ALL EXISTING 4 BULB FIXTURES SHALL USE 2 LED BULBS, INCREASE THE LUMENS PER BULB TO PROVIDE ADEQUATE LIGHTING
3. 70-2'X4' 4 BULB FIXTURES
16-2'X2' 2 "U" BULB FIXTURES
7-4' 2 BULB SURFACE MOUNT CEILING FIXTURES
2-4' 2 BULB FIXTURES IN HALLWAY ARE TO BE REPLACED
3-4' SINGLE BULB WALL MOUNT FIXTURES
6-EXTERIOR HIGH PRESSURE METAL HALIDE WALL MOUNT FIXTURES TO BE REPLACED
4. THE EXISTING PLASTIC LENSES IN THE FOLLOWING ROOMS SHALL BE REPLACED WITH 1/2"X1/2" CHROME LOOK EGG CRATE LOUVERS:
 1. MEETING ROOM 9-2'X4'
 2. CHIEFS OFFICE 4-2'X4'
 3. EMS STORAGE 4-2'X4'
 4. T.V. ROOM 4-2'X2'
 5. HALLWAY 4-2'X4'
 - 8-2'X2'
 6. RADIO ROOM 4-2'X2'
5. REPLACE 2'X4' PLASTIC LENSES IN THE FOLLOWING AREAS:
 1. APPARATUS ROOM-39
 2. KITCHEN-4
 3. TOOL ROOM-2
 4. AUX. STORAGE 2-2'X4'
6. EXTERIOR WALL PACKS SHALL BE AS MANUFACTURED BY:
PHILLIPS LUMILEDS
ELCO LIGHTING
ARCHIPELGO LIGHTING
90-120 WATTS; 5,000K
MIN. 5 YEAR WARRANTY
7. IN THE CLOCK TOWER THERE ARE 4-FLUORESCENT SINGLE BULB FIXTURES TO BE REPLACED
8. EXISTING EXTERIOR WALL SCONCES TO BE REPLACED. REPLACEMENT UNITS SHALL BE PHOTOCELL OPERATED; 30-40 WATTS; 3K-4K LUMENS

No.	Revision/Issue	Date
1	REVISION 1	8/5

Firm Name and Address

Project Name and Address
Village of Oxford
Fire Sattion Renovations
20 Main Street
Oxford, NY 13830

Project	Oxford FD	Sheet
Date	8/5/2025	E 102
Scale	As Noted	

